| | 2015 | Dirt and Grave | l Road | - |
|-----------------------------|---------------------------|-----------------|-----------------|--|
| | | Grant | | Environmentally Sensitive Maintence |
| Municipality | Road Name | Allocation* | Watershed | Practices Installed |
| | | | | Installed 2 high water bypasses, 4 in- |
| | | | | stream stabilization structures, and 3 |
| Cook Township | Lenhart Road | \$15,645.00 | Loyalhanna | broad based dips. |
| | | | | In 2015, the following practices were |
| | | | | installed; 3 crosspipes, 1 through-the- |
| | | | | bank pipe, 2 stream crossings, and 4 |
| | | | | grade breaks. Road surface to be |
| | | | | topped with Driving Surface Aggregate |
| Cook Township | Old Rt. 711 | \$96,800.00 | Loyalhanna | in 2016. |
| | | | | Installed 2 Broad Based Dips, 3 |
| Ligonier Township | Red Arrow Road | \$4,250.00 | Loyalhanna | replaced crosspipes. |
| | | | | |
| | Total: | 116,695.00 | | |
| | | | | |
| | | | | |
| | 201 | 5 Low Volume | Road | |
| | | Grant | | Environmentally Sensitive Maintence |
| Municipality | Road Name | Allocation* | Watershed | Practices Installed |
| | | | | Proposed to install additional |
| | | | | crosspipes and replace existing |
| | | | | crosspipes and install underdrain. To |
| Cook Township | Hoods Mill Road | \$52,991.00 | Loyalhanna | be completed in 2016. |
| | | | | Installed 2 turn out, 5 new crosspipes |
| | | | | and 2 crosspipes relaced, 450 ft |
| | | | | underdrain, and 831 sq yd surface |
| Ligonier Township | Brallier Drive | \$25,613.31 | Loyalhanna | sealed. |
| | | | | Worked off ROW - Installed 1 |
| | | | | Conveyor belt diversions and a |
| | | | | vegetated swale. 1 new crosspipe |
| | | | | installed and 900ft of underdrain |
| Manor Borough | Rowe Road | \$24,893.00 | Turtle Creek | installed. |
| | | | | Installed 4 french matteress and |
| Municipality of Murrysville | Maiolie Road | \$11,159.50 | Turtle Creek | improved road base. |
| | | | | Replaced 1 crosspipe and installed 3 |
| | | | | new crosspipes, installed 1500ft of |
| | | | | underdrain, 20,560 sq yd of surfaced |
| Salem Township | Boggs Hollow Road | \$19,230.00 | Beaver Run | sealed. |
| | | | | |
| | Total: | \$133,886.81 | | |
| | | | | |
| * Gran | t Allocation does not inc | lude in-kind co | ontributions or | total project cost. |